PROJECT: TRIL CENTRE GURGAON (TCG) AT SECTOR 72, GURGAON

BILL OF QUANTITIES FOR SCREED TO TENANT FLOOR -TOWER-B

SNO	ITEM DESCRIPTION	UNIT	Tentative QTY	RATE	AMOUNT
	Note: Following works shall be part of Subcontractor scope and deemed to be included in quoted unit rates; 1) Fixing and dismantling of scaffolding works shall be in Subcontractor scope if required 2) PPE (Pesonnel protection Equipemnts) for Manpower to be engaged by Subcontractor shall be part Subcontractor scope. 3) 100 % compliance (EPF, ESI of Employer & Employee part, Bonus, Welfare fund etc.) shall be part of Subcontractor scope 4) Electricity & water shall be in client scope 5) Labour hutment shall be in contractor scope				
	Screed to Tenant Floor Providing, Pumping and Laying average 75 mm thick Screed using Ready Mix Cocrete of M-20 garde including base prepation/hacking & finished the top surface with floater complete in true lines and level as per specification and drawing and as per the direction of Architect/ Engineer- In – Charge.The Unit rates includes channel shuttering, saw cutting of control joints with polysulphate sealant (from 1st to 13th Floor Tower-B)	sqm	26,422	745	19684390
	Total Net Costs				-
	GST @ 18%				3543190
	Total Gross Costs				23227580